

CLIENT: DARLINGTON BOROUGH COUNCIL

Service: Removal of three boilers



Project Overview:

Durham Lifting were contracted by Darlington Borough Council to remove 3 off 10 tonne boilers from the Town Hall. The location of the boilers were in a confined boiler room with restricted space with the only feasible exit being via a raised louvre into an external car parking area. To ensure continued access for Darlington Borough Council employees the work was completed out of hours.

Statistics:



Delivery time:
2 weeks



Boiler Dimensions:
L 4.5 x W 1.5 x H 1.95 m



Location:
County Durham



Louvre Dimensions:
W 2.3 x H 2.1 m



Team involved:
Design, fabrication, site
service engineers



Weight:
10 tonne



Scope of Work

- 3D model of boiler room to create movement plan
- Design and fabrication of a bespoke skid frame/jack frame
- Installation of skid frame, jack and skate of boilers x 3
- Contract lift onto transport
- Project management for concept to completion

